

**Annexure-A (Staircase)**

<b>Details for Stair Case</b>						
<b>SN</b>	<b>DSR</b>	<b>Item Details</b>	<b>Unit</b>	<b>Rate</b>	<b>Qty</b>	<b>Amount</b>
1	2.25(a)	Local Sand	Cum	700.5	0.243	170.22
2	2.81	Earth Work	Cum	260.3	4.374	1138.55
3	4.1.8	01:04:08	Cum	6812	0.5	3406.00
4	4.1.2	RCC M-20	Cum	8340.85	18.722	156157.39
5	5.22.6	TMT Bar	Kg	107.85	2649.895	285791.18
6	5.9.6	Column Centring	SQM	961.3	76.83	73856.68
7	5.9.5	Beam Centring	SQM	736.4	20.48	15081.47
8	5.9.3	Roof Centring	SQM	927.25	29.33	27196.24
9	5.9.7	Stair Centring	SQM	764.95	35.59	27224.57
10	11.2	B.F.S	SQM	792.05	41.96	33234.42
11	13.4.2	Plastering	SQM	343.65	200	68730.00
12	10.28	P &F SS	Kg	772.4	940	726056.00
13	15.7.3	Dismantling of brick work	Cum	2060.2	2.5	5150.50
14	9.1.1	Wooden door frame	Cum	142949.7	0.2025	28947.31
15	9.20.1	Flush door	SQM	3473.85	10	34738.50
16	9.62.2	Sliding door bolt (250x16)	Each	193.7	4	774.80
17	9.63.2	Door Tower Bolt	Each	69.4	8	555.20
18	9.66.1	Door Handle	Each	39.95	8	319.60
<b>Total</b>						<b>1488528.64</b>

**Annexure-A (Lift Structure)**

<b>Details for lift structure</b>						
<b>SN</b>	<b>DSR</b>	<b>Item Details</b>	<b>Unit</b>	<b>Rate</b>	<b>Qty</b>	<b>Amount</b>
1	2.25(a)	Local Sand	Cum	700.5	0.416	291.41
2	2.81	Earth Work	Cum	260.3	18.116	4715.59
3	4.1.8	01:04:08	Cum	6812	0.833	5674.40
4	4.1.2	RCC M-20	Cum	8340.85	10.676	89046.91
5	5.22.6	TMT Bar	Kg	107.85	1413.361	152430.98
6	6.1.2	Brick Work below PL	Cum	7132.25	9.289	66251.47
7	6.4	Brick Work above PL	Cum	9105.95	11.759	107076.87
8	5.9.6	Column Centring	Sqm	961.3	63.74	61273.26
9	5.9.5	Beam Centring	Sqm	736.4	18.18	13387.75
10	5.9.3	Roof Centring	Sqm	927.25	5.23	4849.52
11	11.2	B.F.S	Sqm	792.05	8.329	6596.98
12	13.4.2	Plastering	Sqm	343.65	235.74	81012.05
13	8.2.2.2	Granite	Sqm	5136.3	18	92453.40
<b>Total</b>						<b>685060.60</b>