

Vasanta College for Women
Rajghat Fort, Varanasi
BOQ

FIRE FIGHTING WORK IN COLLEGE CAMPUS (Auditorium, Staff Room , Gym , Geography Building and upto Home Science Department)				
S. No.	Description Of Items	Unit	Qty	Total Amount
1	100 mm ms pipe medium class and all instalation charges make Jindal and Surya	Meter	150	
2	Hydrant valve 63mm dia complete with heavy duty in the all instalation charges make new age and stop fire and attack fire	Each	6	
3	RRL hose pipe male and female coupling and gi fitting 30 mtr long make new age attack fire and stop fire	pCs	6	
4	Short branch pipe full ss make stop fire and new age and attack fir	pCs	6	
5	House box double door lock with glass door	pCs	6	
6	Providing fixing of swing type first aid fire hose reel concerning to IS:444 complete with heavy duty reel 19 mm dia 30 mtr long 25mm nozzle and all instalation charges	pCs	5	
7	Ball valve 25mm full ss including of all instalation uniyan tee elbow supportin the all instalation charges	pCs	5	
8	10 hp motar taris pump in thea llinstalation charges make kirloskar or similar	pCs	1	
9	100 mm flange	pCs	4	
10	2 core wire 10mm motar in the all instalation	Meter	30	
11	100 mm butterfly in the all instalation charges make kartar	pCs	2	
12	Air release valve and pressure gauge	pCs	1	
13	Fire brigade toway in the all instalation charges	pCs	4	
14	Hydrant flange	pCs	5	
15	Providing & fixing on terrace (at all Floor Levels) polyethylene water storage tank with cover and suitable locking arrangement and making eccasary holes for Inlet , outletand overflow pipe but without fittings and the base support for tank	Per Liter		
16	Civil Works Involved			
	Total			

Note - NOC and Drawing charges if extra should be added in quotaion for the complete work.